

**CONNECTICUT RIVER BASIN**

**ATHOL MASSACHUSETTS**

**ATHOL MANUFACTURING  
DAM**

**MA 00932**

**PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM**

The original hardcopy version of this report  
contains color photographs and/or drawings.  
For additional information on this report  
please email

U.S. Army Corps of Engineers  
New England District  
Email: [Library@nae02.usace.army.mil](mailto:Library@nae02.usace.army.mil)



**DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154**

**MARCH 1979**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER MA 00932	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Athol Manufacturing Dam  NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1979
		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY,  Connecticut River Basin Athol, Massachusetts Millers River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  The dam is a concrete, stone masonry and earth embankment dam. It is 396+ ft. long and the maximum height is 19+ ft. The visual inspection indicated the dam and appurtenant structures to be in generally good condition. It is small in size with a hazard potential of high. It is felt that certain items need attention.		

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

BRIEF ASSESSMENT

Identification No: MA 00932  
Name of Dam: Athol Manufacturing Dam  
Town: Athol  
County and State: Worcester County, Massachusetts  
Stream: Millers River  
Date of Inspection: November 14, 1978

This dam is a concrete, stone masonry and earth embankment dam. It is composed of three main sections. These are a primary spillway, a side channel overflow spillway and an embankment section. The primary spillway is 79 feet long while the overflow spillway is approximately 170 feet long. A sluiceway, which can be used in electric power generation, and wasteway is also incorporated within the limits of this dam. The overall length is 396± feet and the maximum height is 19± feet. There is no record as to when the dam was originally built. Construction modifications were made in 1923, 1936 and 1956. The dam is owned by the Union Butterfield Corporation of Athol, Massachusetts.


The visual inspection indicated the dam and appurtenant structures to be in generally good condition.

The dam is categorized as small in size and its hazard classification is high. According to the Corps guidelines for a Phase I investigation, the test flood is one half

Probable Maximum Flood. The inflow is 20,000 cfs, including an allowance for Birch Hill Dam base flow. The spillways for this dam are capable of passing this inflow without the dam overtopping. It is a run-of-the-river type project. Its storage capacity is very small, thus inflow and outflow are the same. Peak outflow from Birch Hill and peak inflow from the 25 s.m. drainage area are not assumed to coincide. Indepth engineering data was not available and therefore, the assessment of the dam is based primarily on the visual inspection, past performance history, and engineering judgement.

This dam is in generally good condition. It is felt, however, that certain items are in need of attention. These include the removal of small trees and mortaring of cobble joints at the overflow spillway downstream floor; removal of brush and trees at the upstream face of the dam; and removal of overhanging trees and repairing of spalling at the powerhouse canal training walls. The owner should also develop a formal system for warning immediate downstream areas in case of emergency.

After receipt of this Phase I Inspection Report, the above maintenance considerations should be implemented by the owner within 2 years and the warning system should be implemented within 1 year.



*Ronald H. Cheney*  
Ronald H. Cheney, P.E.  
Associate

Hayden, Harding & Buchanan, Inc.  
Boston, Massachusetts

Athol Manufacturing Dam



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Inspections. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation: however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	iii-v
Overview Photo	vi
Location Map	vii

## REPORT

### 1. PROJECT INFORMATION

1.1 General	1
a. Authority	1
b. Purpose of Inspection	2
1.2 Description of Project	2
a. Location	2
b. Description of Dam and Appurtenances	2
c. Size Classification	3
d. Hazard Classification	3
e. Ownership	4
f. Operator	4
g. Purpose of Dam	5
h. Design and Construction History	5
i. Normal Operating Procedures	6
1.3 Pertinent Data	6

### 2. ENGINEERING DATA

2.1 Design Data	11
2.2 Construction Data	11
2.3 Operation Data	11
2.4 Evaluation of Data	11

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	
3.1 Findings	13
a. General	13
b. Dam	13
c. Appurtenant Structures	14
d. Reservoir Area	16
e. Downstream Channel	16
3.2 Evaluation	17
4. OPERATIONAL PROCEDURES	
4.1 Procedures	18
4.2 Maintenance of Dam	18
4.3 Maintenance of Operating Facilities	18
4.4 Description of any Warning System in Effect	18
4.5 Evaluation	18
5. HYDRAULIC/HYDROLOGIC	
5.1 Evaluation of Features	19
a. General	19
b. Design Data	19
c. Experience Data	19
d. Visual Observation	20
e. Overtopping Potential	20
f. Dam Failure Analysis	21
6. STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	22
a. Visual Observation	22
b. Design and Construction Data	22
c. Operating Records	23
d. Post-Construction Changes	23
e. Seismic Stability	23

SectionPage

## 7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1	Dam Assessment	24
a.	Condition	24
b.	Adequacy of Information	24
c.	Urgency	24
d.	Need for Additional Investigation	24
7.2	Recommendations	24
7.3	Remedial Measures	25
a.	Operation and Maintenance Procedures	25
7.4	Alternatives	25


APPENDIXES

APPENDIX A	- INSPECTION CHECKLIST	A-1
APPENDIX B	- ENGINEERING DATA	B-1
APPENDIX C	--PHOTOGRAPHS	C-1
APPENDIX D	- HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1
APPENDIX E	- INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1









PHASE I  
NATIONAL DAM INSPECTION PROGRAM  
NAME OF DAM: ATHOL MANUFACTURING DAM

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region.

Hayden, Harding & Buchanan, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued Hayden, Harding & Buchanan, Inc. under a letter of 28 November 1978 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW 33-79-C-0012 has been assigned by the Corps of Engineers for this work.



b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location

Athol Manufacturing Dam is located in the Town of Athol in Worcester County, Massachusetts. The dam spans the Millers River east of the town center. It is shown on the U.S.G.S Athol, Massachusetts Quadrangle, with coordinates approximately at North 42° 35' 48", West 72° 13' 6".

b. Description of Dam and Appurtenances

The 396± foot dam consists of 3 main sections. These are the primary spillway, the overflow spillway, and the dam embankment. The primary spillway consists of a 79 foot long, 13 foot high stone core concrete capped spillway and a waste gateway. The spillway contains provisions for 2 feet of flashboards. It has a 15 foot concrete abutment founded on rock outcrop on the right side and a 2 foot wide concrete training wall adjacent to the waste gateway on the

left side. The waste gateway is a 6 foot wide by 15 foot high full stop logged structure. Adjacent and to the left of this gateway is the side channel overflow spillway. This structure has a height of 12 to 15 feet, a plan width of about 20 feet and a length of about 170± feet. It is comprised of mortared stone masonry with a concrete cap. Contained within the overflow spillway, at the left end is a 6 foot long by 4 foot deep trash gate which contains slots for stop logs. The dam embankment contains a 1 to 3 foot wide, 19± foot high, 120 foot long concrete wall. The downstream embankment in front of the wall contains rock and miscellaneous soil backfill and is presently highly vegetated. Located at the left end of the embankment is a 12 foot wide, 16± foot high canal sluiceway. The sluice gate controls water to a channelway which can be used in power generation. The gate structure has concrete wingwalls, a metal frame walkway and provisions for raising the gate.

c. size Classification

The dam is categorized as small according to its storage capacity of 360 acre feet and its height of 19 feet.

d. Hazard Classification

This dam has a high hazard classification. Dam failure analysis shows that the mill buildings downstream

of the dam could receive 3 to 4 feet of floodwaters due to dam failure based on Corps guidelines. The stream stage would be about 8 feet. Since this water raise would be rapid and workmen in the lower elevations would have little or no warning the hazard is classified as high.

It must be noted however that the present condition of the river upstream of the dam is heavily silted. This was alluded to by Mr. J. Hayden of Union Butterfield Drill Corporation owners of the dam. Outflow due to dam failure under existing conditions could be considerably less.

e. Ownership

The dam is presently owned by the Union Butterfield Drill Corporation. The dam was originally built by the Athol Manufacturing Company and owned by them until 1962. In 1962 the dam was taken over by Union Twist Drill Company who have since changed their name to Union Butterfield Corporation.

f. Operator

The caretaker of the dam is Mr. James Hayden; superintendant of the Union Butterfield Drill Corporation, Athol, Massachusetts 01331. Telephone (617) 249-3221.

g. Purpose of the Dam

The canal and sluiceway feed water to a electric generation station some 300 feet downstream. This station is put on line when sufficient flow is available. Power is used by the owner. The station was last on line in the spring of 1978.

h. Design and Construction History

There is no record as to when the original dam was constructed. Prior to 1923, the dam had a wooden spillway. The composition of the overflow spillway and embankment at that time is unknown. In 1923, a concrete spillway with wood cribbing outlet, at about the same spillway location, was constructed. In 1927, "cement" head gates were installed for the canal. Further modifications were proposed at that time and shown on plans found at the Worcester County Commissioner's office, however, it is questionable as to whether these improvements were ever instituted. In 1936, the dam was rebuilt resulting in the general overall configuration of the existing structure. The work done in 1936 was designed by C.M. Allen and constructed by M.M. Day in the summer of 1936. Further modifications were made on the spillway face and flashboard facilities in 1956. This work was designed by Howard M. Turner, Consulting Engineer-Boston, Massachusetts. (see Section 6.1b)

i. Normal Operational Procedure

There is no formal operational procedure for this dam. The height of the pond can be regulated at low flow periods by placement of flashboards and stop logs. However, the height of water is usually dependant upon outflow of upstream dams and power generation demand. Flashboards were last installed about two years ago, and power generation last occurred during the spring of 1978.

1.3 Pertinent Data

a. Drainage Area

The drainage area (128,000 acres - 200 s.m.) is generally comprised of wooded, rolling hills. The main stream contributing drainage to this area are the Millers River, Otter River and North Branch Millers River, along with a number of smaller streams. Flow on these streams is regulated by a number of lakes, ponds, small dams, and the U.S. Army Corps of Engineers Birch Hill Flood Control Dam on the Miller River at South Royalston which regulates runoff from a 175 s. area.

Development within the area is generally rural in nature. The cities of Winchendon, Gardner, and Athol, as well as a number of smaller towns, are located adjacent to the major streams. The area is serviced by rail and air facilities, in addition to a number of State highways and local roads.

Directly below the dam is the City of Athol.

There are a number of buildings and homes adjacent to the Millers River as it flows through this city. Downstream of Athol, there is little development adjacent to the river until it nears the City of Orange, about 3.5 miles downstream.

b. Discharge at Dam Site

The outlet works for this dam consist of a 12 foot wide sluiceway channel regulated by a 5 foot high, wooden sluice gate (invert elevation 560), a 6 foot wide by 4 foot high (invert elevation 567) trash gate blocked by stop logs, and a 6 foot wide waste gate (invert elevation 558), also blocked by stop logs. All are operated manually. The primary spillway has provisions for up to 2 feet of flashboards.

The dam was reconstructed in 1936 after the original dam at this site was washed out during the 1936 flood. Modifications were made to the spillway face and flashboard facilities in 1956. Specific records of maximum impoundment and spillway discharge are unavailable. A U.S.G.S. gaging station, No. 1-1640 is located about 7 miles upstream of the dam at South Royalston. This gage, which has a drainage area of 187 square miles, has been in operation since 1939. The maximum discharge recorded at the gage was 4,400 cfs for a stage height of 8.4 feet on April 13, 1940. Floodmarks at the site indicate that the September 1938 flood had a stage height of 15.9 feet.

The discharge capacity over the spillways at the top of dam elevation of 578± is approximately 20,000 cfs. For the test flood of 20,000 cfs (½PMF), the stage elevation at the dam is 578±. (See Section 5.1.e)

c. Elevation (ft. above MSL)

(1)	Streambed at centerline of dam -----	559±
(2)	Maximum tailwater-----	586±
(3)	Upstream portal invert diversion tunnel-----	none
(4)	Normal pool-----	570±
(5)	Full flood control pool-----	N/A
(6)	Spillway crest (ungated)-----	569±
(7)	Design surcharge (Original Design)-----	unknown
(8)	Top Dam -----	578±
(9)	Test flood design surcharge-----	578±

d. Reservoir

(1)	Length of maximum pool----- (½ PMF pool)	2700'
(2)	Length of normal pool-----	400'
(3)	Length of flood control pool-----	N/A

e. Storage (acre-feet)

(1)	Normal pool-----	290
(2)	Spillway crest pool-----	290
(3)	Flood control pool-----	N/A
(4)	Top of dam-----	360±
(5)	Test flood pool-----	360±

f. Reservoir Surface (acres)

- (1) Normal pool-----5.5±
- (2) Spillway crest-----5.5±
- (3) Flood-control pool-----N/A
- (4) Top dam-----12.1±
- (5) Test flood pool-----12.1±

g. Dam

- (1) Type---gravity, concrete and stone masonry structure
- (2) Length-----396'
- (3) Height-----19'±
- (4) Top Width-----Varies-see included plans
- (5) Side Slopes-----vertical U.S. flat D.S.
- (6) Zoning-----none
- (7) Impervious Core-----concrete & stone masonry wall
- (8) Cutoff-----unknown
- (9) Grout curtain-----unknown

h. Diversion and Regulating Tunnel-----none

i. Spillway

- (1) Type-----concrete broad crested weir
- (2) Length of weir-----primary spillway 79'  
overflow spillway 170'
- (3) Crest elevation-----primary spillway 569.1'  
overflow spillway 571.1'
- (4) Gates-----6' wide stop log wasteway
- (5) U/S Channel-----River bed free and open
- (6) U/S Channel-----River bed free and open



j. Regulating Outlets

This dam has 3 regulating outlets. A 12' wide sluiceway channel located at the left end of the dam. Flow through this outlet is regulated by a manually operated 5' high, full width wooden sluice gate. The purpose of this sluiceway is to supply water for electric power generation during periods of high flow. A 6' wide by full height waste gate is located between the primary spillway and overflow side channel spillway. The waste gate is closed to top of overflow spillway by stop logs which can be removed manually. A 6' wide by 4' high trash gate is located near the southern end of the overflow spillway. Stop logs which could be removed manually, are in place for 1/2 the height of gate. In addition, the spillway has provisions for up to 2' of flashboards.

SECTION 2  
ENGINEERING DATA

2.1 Design

Initial design data for construction of the original pre-1923 dam were not discovered. Subsequent dam modification plans were available for the years 1923, 1928, 1936 and 1956. These plans were found at the Worcester County Court House, Engineering Department.

2.2 Construction

No construction data regarding this dam was discovered.

2.3 Operation

The dam is operated by the Union Butterfield Drill Corporation of Athol, Massachusetts. No formal operation outline regarding this dam was available.

2.4 Evaluation

a. Availability

Dam modification plans, Inspection Reports prior to 1972, a County fact sheet and limited County correspondence were available at the Worcester County Court House, Engineering Department. A State Inspection Report from 1972 was available at the State Department of Environmental Quality Engineering Division of Waterways office at Boston, Massachusetts. A 1936 plan showing the then existing location plan and cross sections of the downstream retaining walls was made available by the owner.

b. Adequacy

The lack of indepth engineering data does not allow for a definitive review. Therefore the adequacy of this dam, structurally and hydraulically, can not be assessed from the standpoint of review of design calculations, but must be based primarily on the visual inspection, past performance history, and sound engineering judgement.

c. Validity

The visual field inspection of this dam indicates the external features to agree with those shown on the 1936 and 1956 plans.

SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General

The Phase I field inspection of this dam was made on November 14, 1978. Water was overtopping the main spillway during inspection. The upstream face of the dam could only be inspected above this water surface.

b. Dam

Visual inspection of the dam indicated it is in good condition.

The upstream face of the dam is a reinforced concrete retaining wall, which is in good condition. Cracks that were observed on the face of the wall appeared limited to construction joint locations. The ground surface at the toe of the upstream face of the dam was densely covered with brush and small trees, photo (1). As a result, riprap on the ground surface was not observable.

The crest of the dam is the top of the concrete retaining wall and is about 24 inches wide. Minor cracks, at apparent construction joints, were observed along the crest. No evidence, however, of cracking or misalignment that could be attributed to wall movements was observed.

The downstream slope of the dam is an earth embankment that is relatively flat and covered with hay,

grass and small bushes, photo (2). As a result of the flat topography, the downstream toe was poorly defined. Seeps were not observed on the downstream slope of the dam.

The right abutment of the dam is the junction of the dam and overflow spillway. The junction appeared to be in good condition. The left abutment is a concrete retaining wall that serves as a training wall for the powerhouse canal gate structure.

### c. Appurtenant Structures

#### Primary Spillway

The primary spillway abuts the right side of the river. The structure is bounded on the right by bedrock capped with a concrete block which serves as a training wall and on the left by a concrete training wall, photo(5). The upstream face, crest, downstream face, and apron of the spillway were under water and could not be observed. Flashboards were not present at the time of inspection.

#### Overflow Spillway

The overflow spillway is a masonry structure capped with concrete along the crest and upstream face, photo (4). This structure is bounded to the right by the primary spillway and to the left by the concrete earth-abutment dam. The water level was about 2 feet below the crest of the overflow spillway at the time of inspection. As a result, the upstream face of the spillway

could not be observed. The crest of the overflow spillway had cracks which appeared limited to construction joint locations. Cracks and misalignment of the crest are minor and not considered attributed to movements of the structure. The downstream face of the structure is mortared stone, photo (6). Weep holes present in the downstream face, and several feet below the upstream water surface, did not discharge any water. The downstream toe and channel of the overflow spillway consisted of cobbles grouted in place. The grouted cobble area is generally in good condition with some erosion, small trees and vegetation, photo(4). Seeps were not observed along the toe of the downstream face.

#### Outlet Trash Gate

A stop log structure exists at the junction of the overflow spillway and dam junction. This gate is approximately 6 feet wide by 4 feet high and consists of stop log grooves and stop logs. Stop logs were in place for about  $\frac{1}{2}$  height. Grooves are constructed of steel "H" sections, photo (7).

#### Outlet Waste Gate

This waste gate is a 6' wide by full height outlet consisting of an upstream concrete box inlet structure and downstream stop logs. It is shown to the right of the primary spillway in photo 5. The plans dated 1956 show major

repairs made to the stop log groove on the left side. Stop logs are normally kept in place for full height.

Outlet Sluice Gate (Powerhouse Canal)

This facility consists of concrete training walls, steel framed, hand operated wooden sluice gate and a service walkway. The training walls were in fair to poor condition with some spalling. The sluice gate and walkway appeared to be in good condition and were last used during the spring of 1978.

d. Reservoir Area

The visual inspection showed the area in the vicinity of the dam to be in general agreement with the U.S.G.S. map. Mr. Jim Hayden of Union Butterfield Corporation stated that the upstream river is full of silt and waste from upstream plants; and that water behind the dam is is not very deep. A description of the drainage area is given in Section 1.3 of this report.

e. Downstream Channel

The downstream channel is free and clear. The right side of the channel is stone lined with heavy vegetation. The left side is also stone lined and vegetated with a concrete retaining wall located parallel to the shoreline 10 to 15 feet inward. A steel framed truss roadway bridge is located approximately 500 feet downstream of the dam.

### 3.2 Evaluation

Visual inspection indicates the dam and appurtenant structures to be in good condition, except the training walls of the powerhouse canal, and the area downstream of the overflow spillway. Items observed that could affect the future stability of the dam are:

1. Roots from trees and bushes on the upstream face of the dam could gradually deteriorate the concrete retaining wall.
2. Spalling of powerhouse canal training walls could reduce stability of the walls. Failure of these walls could obstruct flow in the canal.



SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedures

There is no formal written operational procedure for Athol Manufacturing Dam. No flashboards have been used on the main spillway, or the overflow spillway in the past 2 years. Operation of the outlet sluice gate for power generation has not been attempted since the spring of 1978. The Union Butterfield Drill Corporation is responsible for the general maintenance and operation of the dam.

4.2 Maintenance of Dam

There is no formal written maintenance procedure for this dam. No known recent maintenance has been performed on the dam.

4.3 Maintenance of Operating Facilities

There is no formal written maintenance of the operating facilities for this dam. The power generation sluice gate was last operated during the spring of 1978. Operation of the waste gate and installation of flashing for the main spillway has not been attempted in over two years.

4.4 Description of any Warning System in Effect

There are no warning systems in effect at this facility.

4.5 Evaluation

The dam should be inspected every two years by qualified personnel who can identify conditions of concern which if left unchecked could jeopardize the safety of the dam.

SECTION 5  
HYDRAULIC/ HYDROLOGIC

5.1 Evaluation of Features

a. General

This dam basically consists of concrete-stone masonry gravity structure with a 79' long primary spillway, a 6' wide waste gateway and a 170± overflow spillway. In addition, it has provisions for possible electric power generation, trash removal, and release of the upstream pond. The sluiceway for power generation is separated from the primary and overflow spillways by an earth embankment.

The initial inventory sheet classifies this dam as a flood control structure, but there is little additional storage available other than from the flood surcharge behind the dam. The backwater from a roadway bridge several hundred feet downstream of the dam tends to reduce the head differential above and below the dam.

b. Design Data

Hydraulic/Hydrologic data, criteria, and calculations used in the design and subsequent modifications of this dam are not available. Plans showing the proposed and actual modifications of 1927, 1936 and 1956 are available.

c. Experience Data

Information obtained from State and County Inspection Reports indicate that the original dam at this site was washed out during the 1936 flood. Additional data on maximum impound-

ments and discharge rates at this dam are unknown. A U.S.G.S. gage, No. 1-1640 located on the Millers River about 7 miles above the dam at South Royalston, has been in operation since 1939. The record flood for this gage, which has a drainage area of 187 square miles, was 4,400 cfs on April 13, 1940. The gage height was 8.4'. Highwater marks from the 1938 flood indicated a stage height of 15.9' at this site. Since 1942, flow on the river at and below this gage has been regulated by the Birch Hill Flood Control Dam located several miles upstream. Birch Hill regulates flow from a 175 s.m. area.

d. Visual Observations

Visual observations of the drainage area and general vicinity of the dam show them to be in general agreement with U.S.G.S. maps of the area. A description of the drainage area is given in Section 1.3 of this report.

e. Overtopping Potential

The dam carries a small classification for size with a high hazard potential, and as such, should be capable of passing a  $\frac{1}{2}$  PMF. This test flood was computed by obtaining the watershed drainage area from State Inspection Reports and using Corps discharge guide curves. A  $\frac{1}{2}$  PMF inflow of 17,500 cfs from an uncontrolled drainage area of 25 s.m. was developed. Birch Hill's base outflow is assumed to contribute 2,500 cfs, yielding a test flood of 20,000 cfs at elevation 578, approximate top of dam. Birch Hill controls runoff from a 175 s.m. area. Its large storage capacity,

174,000. a-f, would have a significant affect on controlling runoff. Accordingly, peak flows at Athol are not assumed to coincide. Only a 2,500 cfs base flow is applied to the peak discharge from the lower 25 s.m. drainage area. Due to the low storage capacity, inflow equals outflow for this dam. This dam will not overtop under the test flood.

f. Failure Analysis

If the dam should fail with water at elevation 578.1, top of south abutment, 1412 cfs of water would be released from storage. The base flow would be 20,000 cfs. The failure flow then becomes 21,412 cfs. Damage in this case has already occurred, due to the existing high base flow. Failure flow is not significant.

With water at elevation 571, top of side channel overflow spillway, 7340 cfs of water is released from storage. The base flow is 700 cfs over the primary spillway, elevation 569. The failure flow is 8040 cfs. Damage appears to be limited to mill buildings about 1500 to 3000 feet downstream. Between 3 and 4 feet of inundation could occur. The stream stage would be about 8 feet. The dam, 300 feet downstream, could cause a backwater condition and deepen floodwaters. Beyond 3000 feet downstream, no damage appears to occur. The failure flow is dissipated within the river channel. However, buildings in this area are located along the stream channel, close to the level of flooding.

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The visual observations did not disclose any immediate geotechnical or structural stability problems.

b. Design and Construction Data

Available records indicate the Athol Manufacturing Dam was constructed prior to 1923 and underwent extensive rehabilitation in 1923, 1936, and 1956. The reinforced concrete retaining wall serving as the upstream face of the dam was constructed in 1936. A drawing dated May, 1936 and traced in 1960, shows that a "sand fill" was placed to form an earth embankment on the downstream face of the wall. In addition to the retaining wall, a 12 inch thick concrete slab was constructed in front of the powerhouse canal gate structure and an existing stone retaining wall at the left abutment was faced with concrete.

The records indicate the concrete cap on the crest and downstream slope of the overflow spillway existed or was constructed in 1936.

Drawings dated June 20, 1956, show renovation details of the primary spillway. A new reinforced apron was constructed at the downstream toe of the primary spillway. The vertical face of the spillway is a

concrete retaining wall for about 64 feet and granite block wall for 15 feet. In 1956, the renovations included underpinning of the concrete wall footing and placement of 3 inch diameter steel pipes under the footing to relieve water pressures. Available drawings indicate the primary spillway is founded on bedrock.

c. Operating Records

Available records indicate a log apron at the downstream toe of the spillway was washed out in 1955.

A representative of the Athol Manufacturing Company indicated that one time, the dam was overtopped by several feet of water with only surficial damage to the dam.

d. Post Construction Changes

Post construction changes entailed renovations of the dam and appurtenant structures as presented in Section 6.1 b.

e. Seismic Stability

The dam is located in Seismic Zone 2, and according to USCE guidelines, it is assumed that there is no hazard from earthquake loading.

SECTION 7  
ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition

The visual inspection indicates the dam and appurtenant structures to be in generally good condition.

b. Adequacy of Information

The information made available along with the visual inspection, are adequate for a Phase I level of investigation.

c. Urgency

After receipt of this Phase I Inspection Report remedial measures presented in Section 7.3 should be implemented by the owner within 2 years. The exception is the remedial measure 7.3.a (4) which should be implemented within 1 year.

d. Necessity of Additional Investigations

No additional investigations is needed to complete this Phase I inspection.

7.2 Recommendations

There is no need for further engineering studies.

### 7.3 Remedial Measures

#### a. Operation and Maintenance Procedures

1. The small trees growing from between the mortared cobble joints at the overflow spillway downstream floor should be removed. All joints should be mortared as required.

2. The brush and trees located at the upstream face of the dam should be removed and the resulting excavations backfilled.

3. Spalling of the powerhouse canal training walls should be corrected and overhanging trees should be removed.

4. The owner should develop a formal system for warning immediate downstream areas in case of emergency.

5. The dam should be inspected every two years by qualified personnel who can identify areas of concern which left unchecked could jeopardize the safety of the dam.

### 7.4 Alternatives

Not applicable to this dam.



APPENDIX A  
INSPECTION CHECKLIST

## VISUAL INSPECTION CHECK LIST

## PARTY ORGANIZATION

PROJECT Athol Manufacturing DamDATE November 14, 1978TIME 1:00 PMWEATHER cloudyW.S. ELEV. 569.2 U.S.      DN.S.

## PARTY:

- |                      |                          |                                 |
|----------------------|--------------------------|---------------------------------|
| 1. <u>R. Cheney</u>  | <u>H H &amp; B</u>       | 6. <u>                    </u>  |
| 2. <u>D. Vine</u>    | <u>H H &amp; B</u>       | 7. <u>                    </u>  |
| 3. <u>D. Lagatta</u> | <u>GEI</u>               | 8. <u>                    </u>  |
| 4. <u>W. Fisher</u>  | <u>GEI</u>               | 9. <u>                    </u>  |
| 5. <u>J. Hayden</u>  | <u>Union Butterfield</u> | 10. <u>                    </u> |

- | PROJECT FEATURE                 | INSPECTED BY                | REMARKS                     |
|---------------------------------|-----------------------------|-----------------------------|
| 1. <u>Dam embankment</u>        | <u>Daniel P. LaGatta</u>    | <u>                    </u> |
| 2. <u>Control Spillway</u>      | <u>Ron H. Cheney</u>        | <u>                    </u> |
| 3. <u>High Water Spillway</u>   | <u>Ron H. Cheney</u>        | <u>                    </u> |
| 4. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 5. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 6. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 7. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 8. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 9. <u>                    </u>  | <u>                    </u> | <u>                    </u> |
| 10. <u>                    </u> | <u>                    </u> | <u>                    </u> |

PROJECT Athol Manufacturing DamDATE November 14, 1978PROJECT FEATURE Concrete Earth Embankment NAME Ron. H. Cheney  
DamDISCIPLINE Structural Engineer  
Geotechnical EngineerNAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	578.06
Current Pool Elevation	2"± over top of primary spill
Maximum Impoundment to Date	unknown
Surface Cracks	appear limited to construction
Pavement Condition	Not applicable
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	None observed
Horizontal Alignment	None observed
Condition at Abutment and at Concrete Structures	Generally good-some cracking & spalling of concrete
Indications of Movement of Structural Items on Slopes	Not applicable
Trespassing on Slopes	None observed
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection - Riprap Failures	
Unusual Movement or Cracking at or near Toes	Unable to inspect toe of dam & to overflowing
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	Weep holes in overflow spillwa not discharging water
Toe Drains	Not known to exist
Instrumentation System	None
Vegetation	Considerable brush and trees on small embankment in front of concrete wall. Trunk diameters

PROJECT Athol Manufacturing DamDATE November 14, 1978PROJECT FEATURE OutletsNAME Ron H. CheneyDISCIPLINE Structural Engineer  
Geotechnical EngineerNAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p>	<p>No Approach Channel</p> <p>There is a 6' wide by full height stop log waste gate located between the control spillway and the high water side channel spillway. The upstream concrete intake structure was submerged and not inspected. Stop logs in place full height of dam. There is another waste gate 6' wide by 4' high at left end of high water side channel spillway. Stop logs were in place to <math>\frac{1}{2}</math> the height.</p>

PROJECT Athol Manufacturing DamDATE November 14, 1978PROJECT FEATURE SluicewayNAME Ron H. CheneyDISCIPLINE Structural Engineer  
Geotechnical EngineerNAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - CONTROL TOWER</u></p> <p>a. Concrete and Structural</p> <p>General Condition</p> <p>Condition of Joints</p> <p>Spalling</p> <p>Visible Reinforcing</p> <p>Rusting or Staining of Concrete</p> <p>Any Seepage or Efflorescence</p> <p>Joint Alignment</p> <p>Unusual Seepage or Leaks in Gate Chamber</p> <p>Cracks</p> <p>Rusting or Corrosion of Steel</p> <p>b. Mechanical and Electrical</p> <p>Air Vents</p> <p>Float Wells</p> <p>Crane Hoist</p> <p>Elevator</p> <p>Hydraulic System</p> <p>Service Gates</p> <p>Emergency Gates</p> <p>Lightning Protection System</p> <p>Emergency Power System</p> <p>Wiring and Lighting System in Gate Chamber</p>	<p>Control tower at sluice gates sluiceway is steel framed-wood deck. This tower is in generally good condition.</p> <p>System is manually operated. Last operated in Spring of 1978. System appears in generally good condition and operable. Purpose of system is to supply water for electric power generator during periods of high flow.</p>

PROJECT FEATURE Outlets

NAME Ron H. Cheney

DISCIPLINE Structural Engineer  
Geotechnical Engineer

NAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	
General Condition of Concrete	There is no transition and conduit.
Rust or Staining on Concrete	
Spalling	
Erosion or Cavitation	
Cracking	
Alignment of Monoliths	
Alignment of Joints	
Numbering of Monoliths	

## PERIODIC INSPECTION CHECK LIST

PROJECT Athol Manufacturing DamDATE November 14, 1978PROJECT FEATURE Sluiceway ChannelNAME Ron H. CheneyDISCIPLINE Structural Engineer  
Geotechnical EngineerNAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Condition at Joints</p> <p>Drain Holes</p> <p>Channel (Sluiceway to canal to power station)</p> <p>Loose Rock or Trees Overhanging Channel</p> <p>Condition of Discharge Channel</p>	<p>There is no outlet structure</p> <p>Training walls severely spalled in local areas.</p> <p>None observed</p> <p>Condition of Raceway channel is fair to poor. Some small trees on banks above sluiceway walls of no serious concern. Sluiceway channel is open and free.</p>

PROJECT Athol Manufacturing DamDATE November 14, 1978PROJECT FEATURE SpillwayNAME Ron H. CheneyDISCIPLINE Structural Engineer  
Geotechnical EngineerNAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Approach channel is the Millers River itself which was free and open.
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Approach Channel	
b. Weir and Training Walls	
General Condition of Concrete	Water was flowing over the main spillway and therefore the spillway could not be closely inspected. The high water side overflow spillway is of stone masonry with upstream concrete cap. Downstream face and top surface were in good condition. No water discharge from weep holes. Some small trees and erosion at downstream cobble floor. Discharge channel is the Millers River which was free and open. River bottom- is exposed bedrock and gravel. Immediately downstream of overflow spillway, cobbles have been grouted into place.
Rust or Staining	Good.
Spalling	None.
Any Visible Reinforcing	
Any Seepage or Efflorescence	
Drain Holes	
c. Discharge Channel	
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	None.
Floor of Channel	
Other Obstructions	



PROJECT Athol Manufacturing Dam  
PROJECT FEATURE Service Bridge  
DISCIPLINE Structural Engineer  
Geotechnical Engineer

DATE November 14, 1978  
NAME Ron H. Cheney  
NAME Daniel P. LaGatta

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SERVICE BRIDGE</u>  a. Super Structure  Bearings  Anchor Bolts  Bridge Seat  Longitudinal Members  Under Side of Deck  Secondary Bracing  Deck  Drainage System  Railings  Expansion Joints  Paint  b. Abutment and Piers  General Condition of Concrete  Alignment of Abutment  Approach to Bridge  Condition of Seat and Backwall	  There is no service bridge

APPENDIX B  
ENGINEERING DATA

LIST OF AVAILABLE ENGINEERING DATA

1. Construction Drawings dated 1923, 1928, 1936, and 1956.

Location: Worcester County Court House  
Engineering Department  
Worcester, Massachusetts 01009

No design calculations were located.

DESCRIPTION OF DAM		DESCRIPTION OF RESERVOIR & WATERSHED	
<i>Concrete &amp; Crib - old spillway</i>	<i>upstream Conc. Slab</i>	Name of Main Stream	<i>Millers River</i>
<i>Earth - Downstream</i>	<i>Masonry Wall - into River Bed</i>	" " any other Streams	
	<i>305.1</i>	Length of Watershed	
	<i>11.5</i>	Width " "	
ess top	<i>Old crest = 1'-6" - New Crest = 3'-0"</i>	Is Watershed Cultivated	
bottom		Percent in Forests	
ream Slope	<i>Old Crest = abt 1'-6" - New Vertical Face</i>	Steepness of Slope	
im "	<i>New slope = 3:7 - Old Slope = 3:7 <sup>50%</sup></i>	Kind of Soil	<i>Foundation - Hardpan - Boulders</i>
of Spillway	<i>258.17 - Depth - 7.0 - old crest - 79.0 x 2.5</i>	No. of Acres in Watershed	<i>{ 201. Sq. miles = 128,640. Acres</i>
Gates	<i>clean out 6.0 wide x 4.0 - El. at. &amp; 83</i>	" " " " Reservoir	<i>{ checked - 199.2 Sq. miles</i>
n of Gates	<i>South Abt.</i>	Length of Reservoir	
ards used	<i>None</i>	Width " "	
Flashboards or Gates		Max Flow Cu. Ft. per Sec.	<i>100. - 3.7 acres - Tot. 29,000. c.f.</i>
signed by	<i>C.M. Allen - C.E. May 20, 1936.</i>	Head of Flashboards - Low Water	
structed by	<i>M.M. Day - Athol - Summer 1936.</i>	" " " " High "	
structed	<i>New Work by Saunders Eng. Co. 1923 - Nov.</i>		
GENERAL REMARKS		GENERAL REMARKS	
<i>an approved by the Co. Com - 6-2-1936</i>		<i>Inspected: Oct. 25, 1943 - L.O.M.</i>	
<i>unded by the Athol Mfg Co.</i>		<i>" June 14, 1948 "</i>	
<i>spected: 8-8-1936 - L.O.M. G. Alling.</i>		<i>" Mar. 17, 1950 "</i>	
<i>trol - 3-1-1939 - M.A. Casella.</i>		<i>" Feb. 16, 1951 " 6-13-58 L.O.M. T.C.</i>	
<i>3-16, " B.P. St. John.</i>		<i>7-7-58 Supt. Clair.</i>	
<i>spected: 4-13-1940 - L.O.M. Patrol.</i>		<i>1962 - owned by Union Twis.</i>	
<i>" 2-19-1941 - " - V.J. Brown.</i>		<i>Dec. 11 - L.O.M. T.C. Drill Co. - T. Casella</i>	
<i>" 10-27-1942 - M.F. Hunt</i>			
<i>" 5-20- " L.O.M.</i>			

TOWN Athol DAM NO. 02-04

LOCATION 600' Easterly of STREAM Millers River  
Chastnut Hill Rd.

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Green Twist Drill Co. Place Athol Use

Inspected by P.P. - P.P. - EM Date 3-19

Type of Dam Stone - earth - concrete Condition Good

SPILLWAY

Flashboards in Place Recent Repairs

Condition

Repairs Needed Flood Patrol

EMBANKMENT

Recent Repairs

Condition

Repairs Needed

GATES

Recent Repairs

Condition

Repairs Needed

LEAKS

How Serious

DATE:

County Engineer

r 27, 1969 PPP -

Millars River

Union Twist Drill Co.

Flood Patrol - Good condition

No flashboards in place.

'50' Concrete spillway and concrete wall.

TOWN Athol DAM NO. 92-047  
LOCATION 600' easterly of Chestnut Hill Rd. STREAM Millers River

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

(Early) Athol Mfg Co.

Owned by Union Twist Drill Co. Place Athol Use Storage  
Inspected by W.O.L. Date Nov. 24, 1964  
Type of Dam Earth, stone and concrete Condition Good

SPILLWAY

Flashboards in Place 36" of pine boards in the easterly section Recent Repairs   
Condition Also removable boards (4") near the westerly end of the spillway  
Repairs Needed a 5'x5' opening. The splash stone below the spillway  
from the spill have been erected with concrete.

EXTENSION

Recent Repairs There is some small brush on the upstream slope  
Condition Most of the mill buildings have been removed from  
Repairs Needed this old mill site.

GATES

Recent Repairs The canal gates are in good condition - The 2 @  
Condition 5'x8' wood gates to the power house with wood stems  
Repairs Needed and ratchet type lifting apparatus, are partly open

LEAKS

How Serious

DATE:

County Engineer

TOWN Athol DAM NO. 02-04  
LOCATION Athol Mfg Co Dam STREAM Miller R.

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Athol Mfg Co Place Athol Use \_\_\_\_\_  
Inspected by LOM Date Feb. 2, 1959  
Type of Dam \_\_\_\_\_ Condition \_\_\_\_\_

SPILLWAY - Full of ice - No evidence of flood damage  
Flashboards in Place None Recent Repairs 3-4 yrs ago  
Condition Replanked down stream face and bottom all  
Repairs Needed None

EMMENT

Recent Repairs 3-4 yrs ago  
Condition Replanked all  
Repairs Needed \_\_\_\_\_

GATES

Recent Repairs \_\_\_\_\_  
Condition \_\_\_\_\_  
Repairs Needed \_\_\_\_\_

LEAKS

How Serious \_\_\_\_\_

DATE \_\_\_\_\_ County Engineer \_\_\_\_\_



TOWN Athol DAM NO. 02-04  
LOCATION Mullen River STREAM

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Athol Mfg Co. Place Athol Use   
Inspected by Supt. Ed. Clair Date June 13, 1960  
L.P.M. - F.T. Teir  
Type of Dam Earth-Stone & Concrete spillway Condition Good  
stone & concrete in canal to turbine

SPILLWAY

Flashboards in Place Carrying even with Recent Repairs None  
top of Embankment!  
Condition Remove 24" of Flashboards  
Repairs Needed Appears O.K. except too many boards

EMBANKMENT

Recent Repairs None  
Condition appears OK  
Repairs Needed None

GATES

Recent Repairs None - appear OK  
Condition carrying water too high against embankment  
Repairs Needed

LEAKS

How Serious None visible

DATE: June 13, 1960 S. O. Marden County Engi  
E. T. Teir Com. Athol Dept. Public Works

TOWN Athol DAM NO. 02-04  
LOCATION Miller River STREAM \_\_\_\_\_

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Athol Mfg Co. Place Athol Use \_\_\_\_\_  
Inspected by LOM Date Oct. 11, 1958  
Type of Dam \_\_\_\_\_ Condition Good

SPILLWAY

Flashboards in Place None Recent Repairs 2 yrs ago  
Condition Looks good  
Repairs Needed None

WEIR

Recent Repairs \_\_\_\_\_  
Condition Good  
Repairs Needed \_\_\_\_\_

GATES

Recent Repairs Rebuilt gate wing wall  
Condition Good  
Repairs Needed \_\_\_\_\_

LEAKS

How Serious Can't tell acc. flow Hnd

DATE Oct. 11, 1958 S.O. Ward County Engineer

TOWN Athol DAM NO. 0207  
LOCATION \_\_\_\_\_ STREAM Miller River

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Athol Mfg Co. Place Athol Use the  
Inspected by L.O.M. Date July 2, 1958  
Type of Dam Spillway - upstream Condition \_\_\_\_\_  
concrete walls - Embankment

SPILLWAY

Flashboards in Place Yes Recent Repairs Rebld go  
Condition Good whotised  
Repairs Needed None

EMBANKMENT

Recent Repairs None  
Condition Good  
Repairs Needed None

GATES

Recent Repairs Rebuilt one Abt wall to gate structure  
Condition OK  
Repairs Needed None

LEAKS

How serious None visible

Date 7.19.58 L.O.M. County Engin

NO. A. Holt

DAM NO. 02-24

LOCATION Milford River

STREAM

WORCESTER COUNTY ENGINEERING DEPARTMENT  
WORCESTER, MASSACHUSETTS

DAM INSPECTION REPORT

DESIGNED BY Wm. H. Co. PLACE A. Holt USE power

ERECTED BY L. M. Sullivan White DATE May 24 1956

TYPE OF DAM where log apron washed out is poor CONDITION section spillway

SPILLWAY

FLASHBOARDS IN PLACE None RECENT REPAIRS None

CONDITION log apron washed

REPAIRS NEEDED " " to be rebuilt

SPILLMENT

RECENT REPAIRS None

CONDITION Good

REPAIRS NEEDED None

WALL

RECENT REPAIRS None

CONDITION good, except at section near log apron


REPAIRS NEEDED Rebuild concrete wall

AND

HOW SERIOUS None visible


DATE

D. D. White  
COUNTY ENGINEER




Area of Pond: 8.5 Acres.  
Area of Watershed: 201 Sq. Miles  
Elevations shown above sea level.  
G. E. Ailing

Concrete Top Slab and Toe Wall  
to be poured continuously in about  
30 ft. horizontal sections with wedge  
shaped expansion joint with asphalt



Paving to extend at  
least 12 ft. out from  
face of Dam and  
Slope down from 558  
to 556 at waste gate.




Engineered and Approved by:

REDUCED


WORCESTER COUNTY COMMISSIONERS  
WORCESTER COUNTY ENGINEERING DEPARTMENT  
PLAN OF  
RECONSTRUCTION OF DAM  
AT MILLERS RIVER  
ATHOL, MASS.  
FOR ATHOL MANUFACTURING COMPANY  
AS FILED AND APPROVED BY THE  
COUNTY COMMISSIONERS

SCALES AS NOTED


Approved: June 2, 1935 Chairman, Board of County Commissioners	Submitted for Approval: June 2, 1935 County Engineer
Engineered and Approved: S. M. Allen, May 30, 1935 County Commissioner	DAM NO. 22-04




**PLAN OF APRON**  
Scale 1"=8'




**PLAN SHOWING LOCATION OF UNDERPINNING**  
1"=8'




**SECTION A-A**  
Apron detail at old masonry section of spillway




**SECTION B-B**  
1"=2'




**PLAN OF UNDERPINNING PIER**  
1"=2'



**DETAIL OF UNDERPINNING**  
1"=2'



**SECTION THRU PANEL**  
1"=2'




**SECTION THRU APRON**  
1"=2'





REDUCED

**ATHOL MANUFACTURING COMPANY**  
CONSTRUCTION AND REPAIRS TO DAM  
ON MILLERS RIVER  
HOWARD M. TURNER  
CONSULTING ENGINEER  
JUNE 20, 1936  
SCALE AS SHOWN

Sheet 1 of 2 Sheets	
Approved - Aug. 23, 1936 <i>Joseph A. Rogers</i> County Commissioner	Submitted Aug. 23, 1936 <i>C. O. Maxfield</i> County Engineer
Darn No. 02-04	



Note: Exposed faces of steel to be given 2 shop coats of red lead. Damaged areas to be touched up in field with red lead. Field coat of paint to be selected.



REDUCED

ATHOL MANUFACTURING COMPANY  
CONSTRUCTION AND REPAIRS TO DAM  
ON MILLERS RIVER

HOWARD M. TURNER  
CONSULTING ENGINEER  
BOSTON, MASSACHUSETTS

JUNE 21, 1956  
SCALES AS SHOWN

Revised 7-28-56


Sheet 2 of 2 Sheets

Dam No. 02-04





APPENDIX C  
PHOTOGRAPHS



PLAN

HAYDEN, HARDING & BUCHANAN, INC. CONSULTING ENGINEERS BOSTON, MASSACHUSETTS		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LOCATION OF PHOTOGRAPHS ATHOL MANUFACTURING DAM			
ATHOL		MASSACHUSETTS	
		SCALE: NOT TO SCALE	
		DATE: FEBRUARY, 1979.	



PHOTO NO. 1 - Crest of dam  
(top of concrete retaining  
wall) viewed from the left  
abutment. Note dense brush  
and tree growth on upstream  
side of the dam.



PHOTO NO. 2 - Slope of earth embankment downstream of  
concrete dam viewed from the right abutment.





PHOTO NO. 3 - View of concrete retaining wall extending downstream from the dam-overflow spillway junction.



PHOTO NO. 4 - Overflow spillway viewed from junction with the dam. Note spalling of concrete at the bend in the structure and cobbles grouted in place along the toe.





PHOTO NO. 5 - Primary spillway. Note right abutment on bedrock and position of flash board pins.



PHOTO NO. 6 - Downstream face of overflow spillway. Note water is not discharging from drain pipes.





PHOTO NO. 7 - Downstream face of outlet trash gate.



PHOTO NO. 8 - Downstream channel of main spillway viewed from downstream roadway bridge.





PHOTO NO. 9 - Millers River downstream of roadway bridge viewed from bridge.



PHOTO NO. 10 - Downstream view of outlet sluice gate and service walkway. Facility is used in power generation.

APPENDIX D  
HYDROLOGIC AND HYDRAULIC COMPUTATIONS



79.244  
12.12.78  
DD  
MA 12/28



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 1  
JOB Dam Safety Inspect  
SUBJECT Athol Man Co. Dam  
CLIENT COE

## Athol Manufacturing Co. Dam

### Hydraulic Data


from COE Inventory of Dams in U.S. & State & Co.  
Inspection Reports

Dam Crest Length = 309' (Co. Rpt = 305')  
Spillway crest width = 150 (Co. Rpt 79')  
Impoundment Capacity = max = 345 ac-ft  
normal = 290 ac-ft

Structural Height = 20'  
Hydraulic " = 17' (Co. Rpt = 11.5')

### Hydraulic Data from Field investigations & plans

Dam Crest Length = 392' (Inc. Embankment)  
Spillway width = 79'  
Hydraulic Height = 12'



DB NO. 78.244  
DATE 12/21/78  
BY PD  
H'D BY MA



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 1  
JOB Dam Safety  
SUBJECT Athol Man  
CLIENT COE

### SIZE CLASSIFICATION

Height = 12 - Small

Max. Imp. Cap. = 345 x-ft - Small

∴ Use Small Size Classification

### HAZARD POTENTIAL CLASSIFICATION

Developed area of Town of Athol  
located downstream on both sides of River.  
Potential for high property damage and possible  
loss of life exists, depending upon depth  
of flooding downstream.

For now use High Hazard Potential -  
may revise downward later on.

### Test Flood

High Hazard, Small Size

Range :  $\frac{1}{2}$  PMF to PMF

USE  $\frac{1}{2}$  PMF

Total drainage area above dam 200  
5.1

2.44  
2.178  
DD  
MA



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 3

JOB Dam Safety Inspection  
SUBJECT Athol Mfg. Dam  
CLIENT COE

## Test Flood

Birch Hill intercepts runoff from 175 sq. mi. area. Storage capacity 174,000 a-f. Will cause significant reduction of flow at Athol Mfg. Dam. Peak discharge from Birch Hill and that of 25 sq. mi. direct runoff area are not assumed to coincide. Time lag in reservoir & 4 to 5 hr river flow time are significant.

Allow for Birch Hill discharge of 2500 cfs. See Master Manual of Reservoir Regulation Appendix F, Dept of Army

1) Guide Curves (Mtn-Rolling)

For 25 sq. mi. & 1/2 PMF = 17,500 cfs

2) Allowance for Birch Hill


Flow as Base Flow = +2,500.

Test Flood = 20,000 cfs

$Q_p = 20,000$   $EL = 578.0$   $Stor = 350$  a-f - 285 = 65 = .05"  
Storage @ 0

$Q_{p2} = Q_{p1} = 20,000$  cfs

Spillway crest = 3.0' wide



For worst condition: assume all gates closed  
@ time of flood

Also neglect walkway, piers, & gate structure at sluice gate outlet

DATE 11/6/79  
 BY FDD  
 CH'D BY MA



HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS

JOB Dam Safety 1  
 SUBJECT Athol MA  
 CLIENT COE


Determine Storage Capacity of Dam

Normal Pool Storage = 290 ac-ft @ Pool Elev = 570

Planimeter area from USGS Quad sheet (Athol Quad)

Elev.	R <sub>1</sub>	R <sub>2</sub>	R <sub>3</sub>	R <sub>ave</sub>	Area s.m.	acres
570	.07	.05	.06	.06	.00858	5.5
580	.16	.15	.14	.15	.02145	13.7
590	.22	.22	—	.22	.03146	20.1
600	.44	.41	.42	.42	.06006	38.4

Storage: Elev.	Area ac.	Height ft.	Incr Storage ac-ft	Cum Storage ac-ft
570	5.5	—	—	290
580	13.7	10	96	386
590	20.1	10	169	555
600	38.4	10	293	848



## Determine Overflow Capacity of Dam

Have various length "weirs" at several heights and lengths.

To simplify calcs, assume "split weirs" equivalent to weir equal to their combined length.

Also, to simplify determination of weir coefficients use coefficients for broad crested weir.

C from Table 5-3 King's "Handbook of Hydraulics")

Use max length weir = 407'

Use weir formula to determine discharge:

$$Q = CLH^{3/2} \quad \text{with } H \text{ varying, and } C \text{ \& } L \text{ depending upon } H$$

For conditions when have weirs of different heights determine Q for each elev. & use the sum to get total overflow discharge.

Water Elev.	H ft	$H^{3/2}$	C	L ft	Q cfs
569.1	0	0	—	—	0
570.1	1.0	1.0	2.65	7942-91	<u>240</u>
571.1	2.0	2.83	2.72	91	<u>700</u>
571.6	2.5	3.95	2.81	91	1010
	0.5	0.35	2.63	184	170
					<u>1180</u>

JOB NO. 78, 244  
 DATE 12/2/78  
 BY FDD  
 CH'D BY MA



HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS

SHEET NO. 1a  
 JOB Dam Safety  
 SUBJECT Atchafalaya  
 CLIENT COE

Water Elev.	H, ft	H <sup>3/2</sup>	C	L, ft	C
572.1	3.0	5.20	2.92	91	138
	1.0	1.0	2.65	184	491
	0.5	0.35	2.63	15	11
					<u>1880</u>
574.1	5.0	11.78	3.32	91	339
	3.0	5.20	2.92	184	279
	2.5	3.95	2.81	15	171
					<u>634</u>
578.1	9.0	27.0	3.32	91	811
	7.0	18.52	3.32	184	11,3
	6.5	16.57	3.32	15	831
					<u>2030</u>
579.1	10.0	31.62	3.32	91	95
	8.0	22.63	3.32	184	1382
	7.5	20.54	3.32	15	102
	1.0	1.0	2.65	117	310
					<u>24,70</u>
581.1	12.0	41.57	3.32	91	12,5
	10.0	31.62	3.32	184	19,32
	9.5	29.28	3.32	15	1,41
	3.0	5.20	2.92	117	178
					<u>35,1</u>
583.1	14.0	52.38	3.32	91	15,8
	12.0	41.57	3.32	184	25,3
	11.5	39.0	3.32	15	191
	5.0	11.18	3.32	117	434
					<u>47,5</u>

79,244  
10/1/78  
FDB  
MA



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 7  
JOB Dam Safety Inspect  
SUBJECT Athol Man. Dam  
CLIENT COE

Water Elev.	H, ft	H <sup>3/2</sup>	C	L ft	Q cfs.
585.1	16.0	64.0	3.32	91	19,340
	14.0	52.38	"	184	32,000
	13.5	49.60	"	15	2470
	7.0	18.52	"	117	7190
					<u>61,000</u>
586.1	17.0	70.09	3.32	91	21,180
	15.0	58.09	"	184	35,490
	14.5	55.21	"	15	2,750
	8.0	22.63	"	117	8,790
					<u>68,210</u>
587.0	17.9	75.73	3.32	91	22,880
	15.9	63.40	"	184	38,730
	15.4	60.43	"	15	3,010
	8.9	26.55	"	117	10,310
					<u>74,930</u>
588.0	18.9	82.17	3.32	91	24,820
	16.9	69.48	"	184	42,440
	16.4	66.41	"	15	3,310
	9.9	31.15	"	117	12,100
					<u>82,670</u>

JOB NO. 73.244  
 DATE 12/6/78  
 BY FDD  
 CHD BY MA




HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS

JOB Dam Safety  
 SUBJECT Athol No  
 CLIENT C&E

SHEET 1

Stage vs. Discharge Curve for Overflow Weirs  
 Athol Manufacturing Co. Dam

570  
585  
580  
575  
570  
569





78,244  
2/27/79  
FDD  
ma



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 9  
JOB Dam Safety Report  
SUBJECT Arthur Allen Dam  
CLIENT COE

Approximately 1600' downstream of X-Section #5 the Tully River joins the Millers River. Flooding below this point would result from a combination of the flows from both streams. Flooding upstream could also be increased due to the potentially higher backwater at the confluence of these two rivers. The analyses required to determine the effect of the combined flood flows from Millers River and Tully River are beyond the scope of this study. Several homes and structures along North Orange Road and South Main St. in the vicinity of the confluence of these two rivers could suffer flood damage.


JOB NO. \_\_\_\_\_  
 DATE 12/27/70  
 BY E.D.D.  
 H.O. BY W.A.



**HAYDEN, HARDING & BUCHANAN, INC.**  
 CONSULTING ENGINEERS  
 BOSTON - MASSACHUSETTS

JOB Don. Sect. 1  
 SUBJECT Arthur J. Man  
 CLIENT C.E.

SHEET NO. 1



244  
127/78  
DD  
MA



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 11

JOB Dam Safety Impact  
SUBJECT Atchafalaya Dam  
CLIENT COE

## Past Flood and Other Hydrologic Data

Gage No.	Gage Location	D.A. sq. mi.	Peak Flood Discharge	Date	Comments
1-1620	Millers River near Winchendon, Mass.	83	8,500 cfs	9/22/38	'38 CSM = 102 cfs/sq. mi.
1-1646	Millers River @ S. Ponolston, Mass.	187	4,400 cfs. (Gage Ht = 8.8')	4/13/40	MAX. GAGE EL. RECORD = 15.9' 9/21 or 22/39; no discharge available
1-1665	Millers River @ Farky, Mass.	375	29,000 cfs	9/22/38	'38 CSM = 77 cfs/sq. mi.

## Maximum Probable Flood Flows - NED Reservoirs nearby

Project	D.A. sq. mi.	MPF cfs/sq. mi.	Discharge cfs.
Tully	50	940	47,000
Birch Hill	175	505	88,500

JOB NO. 78.244.1  
 DATE 1/26/79  
 BY MA  
 CH'D BY ✓ RDD



HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS


SHEET NO.           
 JOB Dams  
 SUBJECT A-101  
 CLIENT Co-73

## Failure Analysis

$$Q_F = \frac{8}{27} (.4 \times 263) \sqrt{32.2} (4)^{1.5} = 1412 \text{ cfs}$$

Top Dam = 578.1  
 River Bed = 559.1

Flow = 20300 cfs just  
 prior to failure



<u>Section #</u>	<u>Base Q</u>	<u>Failure Q</u>	<u>Base Elev</u>	<u>Fail El</u>
1	20260	21672	570.0	570.3
2	20260	21672	559.0	559.3
3	15200	16259	537.5	538
4	9200	9840	524.5	525
5	5300	5669	516.5	517


$Q_{P1} = 20300$   $Star_1 = 360 \text{ ft} \text{ for } 0.034''$   
 $Q_{P2} = 22,227$   $Q_{P3} = 20260 \pm$

Damage Due to Flooding prior to dam Fa.

Water @ 571 (TOP OF OVERFLOW SPILLWAY)

$Q_{base} = 700 \text{ cfs}$  depth in stream  
about 0.5 ft.

$$Q_F = \frac{8}{27} \times 105 \times \sqrt{32.2} \times (12)^{1.5} = 7340 \text{ cfs}$$




Sect	Base Q	Fail Q	Base Elev	Fail Elev
1	700	8040	555.5	563.5
2	700	8040	540.5	555
3	525	6553	543.5	554
4	320	4000	517.5	522.5
5	185	2300	510.5	514.5

Damage due to dam failure:

Sect 1 nothing  
Sect 2 mill bldgs @ el 552± WATER DEPTH 3±  
" 3 mill bldgs @ el 550 " " 4±  
" 4 nothing  
" 5 nothing

dam @ Sect 3 could cause high backwater -  
more flooding, need bldg elevations!



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS


**ATHOL MANUFACTURING DAM**

ATHOL

MASSACHUSETTS

SCALE: 1" = 250,000"

DATE: FEBRUARY, 1979.



APPENDIX E

INFORMATION AS CONTAINED IN THE  
NATIONAL INVENTORY OF DAMS